

(A) FOUNDATION AND GROUND FLOOR PLAN

SCALE: 1/8" = 1'-0"

NOTES:

1. PRECAST SLAB SHALL BE DESIGNED FOR FOLLOWING LOAD.
   DEAD LOAD - SELF WEIGHT OF MEMBER
   SUPER IMPOSED DEAD LOAD - 37 PSF (INCLUDES 2 1/2" TOPPING) GYMNASIUM AND TENNIS AREA
   - 57 PSF (INCLUDES 2 1/2" TOPPING) FOR CLASS ROOM AND OFFICE
   LIVE LOAD - 100 PSF GYMNASIUM AREA
   - 50 PSF CLASS ROOM AND OFFICE
   CONTRACTOR SHALL SUBMIT PRECAST SLAB SHOP DRAWINGS WITH SLAB LAYOUT AND CALCULATIONS FOR REVIEW.
2. WALL MARKS SW 1, SW 2, SW 3, SW 4 ON PLAN ARE SHEAR WALLS, REFER SHEET S 4.0 FOR DETAILS.
3. REFER SHEET S 0.0 FOR GENERAL NOTES AND SHEET S -0.1 , S 0.2 FOR TYPICAL DETAILS.
4. REFER SHEET S 3.0 FOR ANCHOR BOLTS AND COLUMN SCHEDULE.
5. REFER SHEET S 4.0 FOR MOMENT AND BRACE FRAMES, SHEAR WALL ELEVATIONS.

N

APPROVED
FOR BUILDING PERMIT ONLY
CITY OF HOUSTON
CODE ENFORCEMENT DIVISION

The owner is responsible for compliance with the Building Code. Such approved plans and specifications shall not be changed, modified or altered without authorizations from the building official, and all work shall be done in accordance with the approved plans.

NO. 368

Community Family Centers
Centros Familiares de la Comunidad

THATS ARCHITECTURE
2402 COMMONWEALTH #100, HOUSTON, TX. 77006
TELEPHONE 713/222-1406 FAX 713/222-1506

STATE OF TEXAS
R.D.PATEL
85114
LICENSED
PROFESSIONAL ENGINEER
8/7/06

John P. McGovern, M.D.
Community Sports & Recreation Building
7318 AVENUE F
HOUSTON, TEXAS 77011

ISSUES & REVISIONS

1	8/7/06	ISSUED FOR PERMIT

SHEET TITLE

FOUNDATION AND GROUND FLOOR FRAMING PLAN

PROJECT NO. 2001-30
SCALE AS NOTED

SHEET NUMBER

S 1.0